

# Oldcastle NC Project

## Back in October of 2001.....

The Oldcastle Precast plant of Concord, NC was devastated by a fire that swept through the entire facility. But in the face of misfortune, Oldcastle decided to rebuild immediately. And they decided to take full advantage of the situation by upgrading with the best in the industry – Advanced Concrete Technologies.



### **Project Highlights**

- 60 CU TD/Hour Output
- SCC Production
- 2 Min./Batch
- 10X faster than old plant
- Shorter production day—labor savings



WE ADD PROFITABILITY TO THE MIX.

### **Oldcastle NC Specs**

MobilMat MO 80/4-PCS

Capacity for 4 bins with 270 tons aggregate storage

HYDROMAT

2 moisture probes in aggregate bins

PCS Computer Control System including costing, maintenance, network to server

In-ground truck dump hopper

Automatic aggregate feeding

Double split wall cement silo — 125 tons

Automatic mixer cleaning

Ground-mounted dust collection

